EXISTING STAGE 3 CE(10) CE(9) 106 87 702m² 702m² 107 674m² 105 88 108 674m² NOTE: OVERHEAD-POWER ALONG HILLS RD. TO BE REMOVED IN STAGE 7. 104 663m² 663m² 109 674m² 103 663m² 90 663m² 110 658m² ERRION 91 102 663m² 663m² ROAD LOCATIONS SHOWN -FOR FUTURE STREET 111 667m² TREES ALONG HILLS ROAD. AS AGREED WITH COUNCIL IN STAGE 3, 92 101 FUTURE STAGE 663m² 663m² TREES ALONG HILLS ROAD ARE TO BE INSTALLED (AND BONDED FOR 112 MAINTENANCE AS REQUIRED) IN 674m² CONJUNCTION WITH 93 100 STAGE 7 WORKS ONCE OVERHEAD 702m² 702m² POWER IS REMOVED. SPECIES TO BE DETERMINED AND DOCUMENTED WITH STAGE 7 LANDSCAPE 113 674m² 99 94 702m² 702m² 114 95 674m² 98 663m² 663m² TEMPORARY ASPHALT PATH — AROUND POWER POLE AS PER CIVIL PLANS. TO BE REMOVED AND REPLACED WITH STRAIGHT CONCRETE SECTION ON 115 96 REMOVAL OF OVERHEAD 663m² POWER IN STAGE 7. 663m² **FUTURE STAGE FUTURE STAGE**

PLANT SCHEDULE AND QUANTITIES - ADVANCED TREES

KEY	BOTANIC NAME	COMMON NAME	SPACING	POT SIZE BAG SIZE	HT. AT PURCHASE	CALIPER (DBH)	APPROX. HT. & SPR.	QTY	REMARKS
CE	CORYMBIA EXIMIA 'NANA'	DWARF YELLOW BLOODWOOD	AS SHOWN	MIN. 45 litre	1.8m MIN.	30mm MIN.	9x5m	19	HARDY NATIVE SPECIES
							TOTAL:	19	

ALL TREES TO BE INSTALLED AS PER STREET TREE PLANTING DETAIL (FOUR STAKE), SHEET LA-02.

PLAN LEGEND



PROPOSED ADVANCED STREET TREE

REFER PLANT SCHEDULE AND STREET TREE PLANTING DETAIL (FOUR STAKE).

NOTE: FINAL LOCATION OF STREET TREES TO BE SET OUT AND APPROVED ON-SITE PRIOR TO INSTALLATION. TREE LOCATIONS SHOWN ON THIS PLAN ARE TO BE USED AS A GUIDE ONLY, AND WILL REQUIRE ADJUSTMENT ON-SITE TO FIT IN WITH ABOVE AND BELOW GROUND FIXTURES AND

NOTE: TREES TO BE LOCATED MINIMUM 4.0m OFFSET FROM STREET LIGHTING AND 2.5m OFFSET FROM ELECTRICAL

ALL ELECTRICAL JOINT LOCATIONS ARE TO BE IDENTIFIED BY THE CONTRACTOR FROM AS CONSTRUCTED PLANS, AND TREE LOCATIONS ADJUSTED ACCORDINGLY.



FUTURE STAGE 7 STREET TREES

LOCATION FOR FUTURE STREET TREES ALONG HILLS ROAD. AS AGREED WITH COUNCIL IN STAGE 3, TREES ALONG HILLS ROAD ARE TO BE INSTALLED (AND BONDED FOR MAINTENANCE AS REQUIRED) IN CONJUNCTION WITH STAGE 7 WORKS ONCE OVERHEAD POWER IS REMOVED. SPECIES TO BE DETERMINED AND DOCUMENTED WITH STAGE 7 LANDSCAPE PLANS.



PROPOSED SEEDED LAWN SURFACE

REFER SURFACE FINISHES SCHEDULE SHEET LA-02.



PROPOSED STREET LIGHT / **ELECTRICAL JOINT**

REFER ELECTRICAL DRAWINGS FOR FURTHER

NOTE: MINIMUM TREE OFFSETS ARE TO BE OBSERVED, SHOWN DASHED. TREES TO BE LOCATED MINIMUM 4.0m OFFSET FROM STREET LIGHTING AND 2.5m OFFSET FROM ELECTRICAL JOINTS.

ALL ELECTRICAL JOINT LOCATIONS ARE TO BE IDENTIFIED BY THE CONTRACTOR FROM AS CONSTRUCTED PLANS. AND TREE LOCATIONS ADJUSTED ACCORDINGLY.

PLANT PALETTE



Corymbia eximia 'Nana'



PLANNING PERMIT NO

DS/880/2014 - CITY OF GREATER BENDIGO

- It is the responsibility of the person/s undertaking the works to check the location and depth of all services prior to
- center the location and depth of all services prior to commencing on site.

 The person/s undertaking the works shall be liable for any damage to services during construction works.

 Any problems or discrepancies with these drawings must be referred directly to the landscape architect, including any
- species substitution.

 All dimensions are in millimetres unless otherwise noted. Written dimensions take precedence over scaling.

 • Design and drawings © Scamp Landscape.

LANDSCAPE PLAN (1 OF 2) **DISCOVER MARONG STAGE 4** HILLS ROAD MARONG

CLIENT: ARBOR ESTATES PTY. LTD.

DRAWING NO	REVISION
LA-01 (1 OF 2)	A - 28.08.2018

PRINT ISSUE JOB NO FOR TOWNPLANNING 14-045

SCALE 1:750 @ A3




NORTH




Brendan Bartlett Landscape Architect BLArch, Reg'd Landscape Architect AILA

REFER CONSTRUCTION **NOTES** SHEET LA-02



SURFACE FINISHES SCHEDULE

PLAN SYMBOL SECTION (NOT TO SCALE)



EVENLY SPREAD KIKUYU LAWN SEED. WITH LAWN STARTER FERTILIZER (YATES OR NEAREST APPROVED EQUIVALENT) AS PER MANUFACTURERS INSTRUCTIONS. IF SEEDING BETWEEN MARCH - SEPTEMBER, APPLY KIKUYU / PERENNIAL RYEGRASS BLEND TO AID ESTABLISHMENT. LIGHTLY RAKE AND WATER IN.

50-75mm DEEP SITE TOPSOIL, FREE OF WEEDS AND DEBRIS. TOPSOIL TO BE INSTALLED BY CIVIL CONTRACTOR, OR SUBGRADE TO BE LEFT DEPRESSED FOR ADDITION OF TOPSOIL BY LANDSCAPE CONTRACTOR. MIX AND CULTIVATE THE TOPSOIL LAYER WITH THE UNDERLYING SUBGRADE TO INCREASE ACCESSIBLE ROOT DEPTH.

CULTIVATE AND DECOMPACT SUBGRADE.

CONSTRUCTION NOTES:

ALL TREES TO BE UN-DEFORMED DISEASE-FREE SPECIMENS WITH A SINGLE LEADER AND HEALTHY, UN-POT BOUND ROOT SYSTEM. ANY IMPORTED TREES FROM TROPICAL / SUB-TROPICAL / HILLS CLIMATES MUST BE HARDENED OFF TO LOCAL CONDITIONS WITH REDUCED WATERING FOR A PERIOD OF FOUR TO SIX WEEKS PRIOR TO INSTALLATION. ALL TREES TO BE INSTALLED AS PER APPROPRIATE PLANTING DETAIL. FINAL LOCATION OF TREES ARE TO BE SET OUT AND APPROVED ON-SITE PRIOR TO INSTALLATION. TREE LOCATIONS SHOWN ON THIS PLAN ARE TO BE USED AS A GUIDE ONLY, AND WILL REQUIRE ADJUSTMENT ON-SITE TO FIT IN WITH ABOVE AND BELOW GROUND FIXTURES AND SERVICES.

WEED CONTROL

ALL NATURE STRIP AND ROUNDABOUT AREAS ARE TO BE TREATED WITH A NON-RESIDUAL GLYPHOSATE-BASED HERBICIDE, MIN ONE WEEK PRIOR TO PLANTING AND/OR SEEDING. APPLY AS PER MANUFACTURERS INSTRUCTIONS, WITH TWO APPLICATIONS SPACED 1-2 WEEKS APART. IN DRY WEATHER, AREAS ARE TO BE WATERED ONE WEEK PRIOR TO INITIAL APPLICATION TO ENCOURAGE GERMINATION.

GENERAL CONSTRUCTION:

LOCATIONS OF UNDERGROUND AND OVERHEAD SERVICES SHALL BE CHECKED AND CONFIRMED BY THE CONTRACTOR PRIOR TO ANY EXCAVATION AND/OR CONSTRUCTION. PLANT LOCATIONS MAY REQUIRE MODIFICATION AS REQUIRED. ALL WORK TO CONFORM TO CURRENT BUILDING CODE OF AUSTRALIA, AND RELEVANT AUSTRALIAN STANDARDS. REFER ANY DISCREPANCIES INCLUDING QUANTITIES, AND UNAVAILABILITY OF MATERIALS INCLUDING PLANTS TO THE LANDSCAPE ARCHITECT FOR DECISION AND/OR SPECIES OR MATERIALS SUBSTITUTION.

REFER TO ADDITIONAL GENERAL NOTES THIS SHEET.



PLANNING PERMIT NO

DS/880/2014 - CITY OF GREATER BENDIGO

NOTE

- It is the responsibility of the person/s undertaking the works to check the location and depth of all services prior to commencing on site
- The person's undertaking the works shall be liable for any damage to services during construction works.
 Any problems or discrepancies with these drawings must be referred directly to the landscape architect, including any
- All dimensions are in millimetres unless otherwise noted
- Written dimensions take precedence over scaling

 Design and drawings © Scamp Landscape.

LANDSCAPE PLAN (2 OF 2) **DISCOVER MARONG STAGE 4** HILLS ROAD MARONG

CLIENT: ARBOR ESTATES PTY. LTD.

DRAWING NO REVISION LA-02 (2 OF 2) A - 28.08.2018

PRINT ISSUE JOB NO FOR TOWNPLANNING 14-045

